

Bid Bulletin for Solicitation Number: **24-SBC-003**

Reference Number	10504763
Procuring Entity	SMALL BUSINESS GUARANTEE AND FINANCE CORPORATION - MAKATI CITY
Title	Structured Cabling for SBCorp's Office of the President, Board Room, ManCom Room and 18th Floor Lobby
Area of Delivery	Metro Manila

FROM	TO
<p>STRUCTURED CABLING</p> <ul style="list-style-type: none"> • For OP, Board Room, 18th Lobby and Mancom Area Nodes: 15 • <u>Forty-five (45) UTP Cable runs between data cabinet and individual workstations.</u> • Category 6 UTP Cable • UTP cable color: White • Faceplate with RJ45 LAN port per workstation Three-meter patch cord per workstation • Patch cords for patch panel connection to the switch • <u>Twenty-two (22) pcs of 3-meter patch cord as spares</u> • Conduit must be Electrical Metallic Tubing (EMT) Support materials and accessories must be in accordance with the latest building renovation guidelines. • issued by the building administration. • Tagging and labelling per cable, patch panel port and workstation faceplate. • Documentation, including proposed plan reflected on the floor plan and As-Built Drawing. • <u>Two (2) pcs patch panel (1RU each patch panel, 24 ports per panel).</u> • <u>Two (2) pcs cable manager</u> • Mounting accessories (e.g., nuts and bolts) for patch panels and cable managers 	<p>STRUCTURED CABLING</p> <ul style="list-style-type: none"> • For OP, Board Room, 18th Lobby and Mancom Area Nodes: 15 • Fifteen (15) UTP Cable runs between data cabinet and individual workstations. • Category 6 UTP Cable • UTP cable color: White • Faceplate with RJ45 LAN port per workstation Three-meter patch cord per workstation • Patch cords for patch panel connection to the switch • Fifteen (15) pcs of 3-meter patch cord as spares • Conduit must be Electrical Metallic Tubing (EMT) Support materials and accessories must be in accordance with the latest building renovation guidelines. • issued by the building administration. • Tagging and labelling per cable, patch panel port and workstation faceplate. • Documentation, including proposed plan reflected on the floor plan and As-Built Drawing. • One (1) pc. patch panel (1RU each patch panel, 24 ports per panel). • One (1) pc. cable manager • Mounting accessories (e.g., nuts and bolts) for patch panels and cable managers